

June 13, 2022

Page 1 of 1
Our File: 306-1981

**TOWN OF OLIVER
OKANAGAN STREET SANITARY SEWER REPLACEMENTS**

**CONTRACT DOCUMENTS AND SPECIFICATIONS
ADDENDUM # 2**

This Addendum is being issued prior to the closing of Tenders and is intended as clarification and/or revision of the Contract Documents. This Addendum shall become an integral part of the Contract Documents and Tenderers shall acknowledge receipt on the appropriate page of the Form of Tender.

1. Upon request we can provide an FTP link to three (3) CCTV files completed in 2016 indicating the state of the sanitary sewers to be lined. The awarded contractor is still required to complete item 2.2.1– “CCTV inspection c/w cleaning (pre-liner)” of the Contract Tender Documents.
2. Contract item 2.2.8-“Manhole Rehabilitation c/w cleaning & CIPP lining” shall include:
 - a) Surface preparation/cleaning of inside manhole to remove unsound concrete, dirt, dust, oil, and other debris using high pressure(±3500psi) water blasting.
 - b) Mixing of Geoliner Geopolymer mortar as supplied by Parson Environmental Products Inc.
 - c) Application of Geoliner Geopolymer mortar per manufacturer’s instructions.



Todd Turnbull, AScT, CPWI 3

TT/jr

Within FTP link::

- CCTV map.jpg – 2016 CCTV/Numbering overall map
- D-242-D-449.MPG – 2016 CCTV relating to manholes EX1 to EX2
- D-449-D-195.MPG – 2016 CCTV relating to manholes EX2 to EX3
- D-247-D-242.MPG – 2016 CCTV relating to manholes S3 to EX1
- Geoliner Geopolymer mortar specification brochure

R:\Clients\300-399\306\306-1981\07 Contract\Okanagan Street Sanitary Sewer Replacements\Addendum 2\306-1981-Addendum 2-2022 06 13.docx